



- EDGE CONDITIONS LEGEND:
- E1 - 0'-0" (H) TO 0'-10" (H) (VARIES) PARAPET WALL. REMOVE EXISTING EDGE METAL AND WALL FLASHINGS. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE. INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0001)
 - E2 - GRAVEL STOP EDGE METAL, REMOVE EXISTING EDGE METAL, INSTALL NEW WOOD BLOCKING TO MATCH HEIGHT OF NEW ROOF SYSTEM & NEW GRAVEL STOP EDGE METAL W/ FULLY ADHERED FLASHING (SEE DET 0002)
 - E3 - 1'-0" (H) WALL FLASHING, REMOVE ALL FLASHINGS FULLY ADHERE NEW WALL FLASHING, INSTALL TERM BAR, SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING W/ SEALANT JOINT (SEE DET 0003)
 - E4 - REMOVE EXIST. DRIP EDGE METAL (AND EXISTING GUTTER) INSTALL NEW WOOD BLOCKING AND TAPERED EDGE STRIP TO MATCH HEIGHT OF NEW ROOF SYSTEM, TO PROMOTE DRAINAGE INTO GUTTER AND PREVENT PONDING ALONG ROOF EDGE. INSTALL NEW 6' X 6' BOX GUTTER W/ (2) 4'X4' DOWNSPOUTS (SEE DET 0004)

- PENETRATIONS LIST:
- CURBS:
- A - 8' X 36'6" RTU
 - B - CHILLER UNIT ON (2) 15' LONG EQUIPMENT SUPPORT CURBS
 - C - CHILLER UNIT ON (2) 19' LONG EQUIPMENT SUPPORT CURBS
 - D - 5'6" X 8' RTU
 - E - 4' X 6'6" RTU
 - F - 3' X 5' RTU
- ROOF HATCH - 3' X 8'6"
- PIPES
- 1" - 14
 - 2" - 1
 - 3" - 2
 - 4" - 10
- VENT STACKS
- 8" - 4
 - 10 - 3
- RTV'S
- 1'6" X 1'6" - 1
 - 1'9" X 1'9" - 1
- KITCHEN EXHAUST FANS
- 1'9" X 1'9" - 1
 - 2' X 2' - 1
 - 2'6" X 2'6" - 1
- SATELLITE DISH PADS (SET ON WALK PADS)
- 4' X 4' - 1
 - 7' X 7' - 1
- CONDENSER ON 1'6" X 3' EQUIPMENT PAD - 1 (SET ON WALK PADS)
- 1'6" X 3'6" UTILITY HOOD - 1



DISCLAIMER
ALL DEAD, DESIGNED ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY AND ARE THE PROPERTY OF ROOFINGPROJECTS.COM AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH LOGOS, DESIGNS, ARRANGEMENTS OR MARKS SHALL BE USED BY OR DISCLOSED TO ANY PARTISAN WHATSOEVER WITHOUT THE WRITTEN PERMISSION OF ROOFINGPROJECTS.COM.
WRITTEN DIMENSIONS ON THIS DRAWING SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTOR SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS.

No.	Revision/Issue	Date

Firm Name and Address
 RoofingProjects-com
 17 High Street
 Suite 301
 Norwalk, CT
 06851

Project Name and Address
 2026
 Shaws #2532
 199 N Main St
 Lancaster, NH 03584

Project	Sheet
Date May 4, 2026	1
Scale 3/32" = 1'-0"	

ROOF PLAN

SECTION "C"
 (APPROX. 4,500 SQ. FT.)
 (ALL SHINGLE AREAS ON FRONT OF SHAW'S STORE)

SECTION "D"
 (APPROX. 1,100 SQ. FT.)
 (REMAINDER OF SHINGLE AREAS ON FRONT OF ADJACENT RETAIL STORES)

SECTION "C" SHINGLES UP TO THIS VALLEY

SECTION "D" SHINGLES UP TO THIS VALLEY