



- PENETRATIONS LIST:**
- CURBS:**
- A - CHILLER UNIT ON (2) 8' LONG EQUIPMENT SUPPORT CURBS WITH (1) 16" X 26" UTILITY HOOD
 - B - 4' X 6' RTU
 - C - 6' X 9' RTU
 - D - 4'6" X 7'6" RTU
 - E - 5'6" X 5'6" RTV
 - F - CHILLER UNIT ON (2) 26' LONG EQUIPMENT SUPPORT CURBS
 - G - CHILLER UNIT ON (2) 14' LONG EQUIPMENT SUPPORT CURBS
 - H - CHILLER UNIT ON (2) 20' LONG EQUIPMENT SUPPORT CURBS
- ROOF HATCH 3' X 3'6"**
- PIPES**
- 1" - 17
 - 2" - 1
 - 3" - 4
 - 4" - 16
 - 5" - 6
- VENT STACKS**
- 2' X 2' - 6
- RTVS**
- 19" X 19" - 1
 - 2' X 2' - 7
 - 26" X 26" - 2
 - 3' X 46" - 2
- KITCHEN EXHAUST FANS**
- 2' X 2' - 2
 - 3' X 3' - 1
- 8" X 8" SATELLITE DISH BASE CURB - 1**
- 26" X 26" GOOSE NECK VENT - 1**
- 2' X 3' UTILITY HOOD - 2**
- 26" LONG EQUIPMENT SUPPORT CURBS - 3**
- 3' X 46" ABANDONED CURB - 1 (REMOVE CURB, CLOSE OPENING IN DECK, INFILL INSULATION TO MATCH HEIGHT OF ROOF SYSTEM AND ROOF OVER)**
- DOWNSPOUTS - 6 INSTALL WALK PAD AT DISCHARGE POINT**

EDGE CONDITIONS LEGEND:

- E1 - 8" (H) TO 5'-3" (H)(VARIES) PARAPET WALL. REMOVE EXISTING METAL COPING, WALL FLASHINGS AND ANY LOW METAL COUNTER FLASHING. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE. INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0001)
- E2 - 8" TO 1'-4" (H) WALL FLASHING. REMOVE FLASHINGS. INSTALL 1/2" DENS DECK TO INSIDE FACE OF WALL. INSTALL FULLY ADHERED NEW WALL FLASHING. INSTALL TERM BAR, SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING WITH SEALANT JOINT TIGHT TO BOT. OF EIFS (SEE DET. 0002)
- E3 - 4'-0" (H) SLOPED SHINGLE AREA. INSTALL 1/2" DENS DECK OVER EXISTING SHINGLES. FULLY ADHERE NEW WALL FLASHING OVER TOP AND DOWN FRONT FACE. INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0001)
- E4 - EXISTING AREA DIVIDER REMOVE EXISTING FLASHINGS. INSTALL 1/2" DENS DECK TO INSIDE FACE OF WALL. FULLY ADHERE NEW FLASHING UP OVER BOTH SIDES AND TIE INTO FIELD MEMBRANE ON BOTH SIDES
- E5 - 1'-0" (H) WALL FLASHING. REMOVE ALL FLASHINGS LEAVING METAL COUNTER FLASHING TO REMAIN. INSTALL 1/2" DENS DECK TO INSIDE FACE OF WALL. HOLDING TOP 4" DOWN FROM BOTTOM EDGE OF EXIST. METAL. FULLY ADHERE NEW WALL FLASHING. INSTALL TERM BAR AND SEALANT TIGHT TO EXISTING FLASHING SUBSTRATE. INSTALL SLIP FLASHING TO BACKSIDE OF EXISTING COUNTERFLASHING (SEE DET. 0003)

REMOVE EXISTING DRIP EDGE AND GUTTER AND REPLACE WITH NEW DRIP EDGE AND 6" X 6" BOX GUTTER WITH NEW DOWNSPOUTS TO MATCH EXISTING CONFIGURATION AND LOCATIONS AS PART OF SECTION C SHINGLE REPLACEMENT (ALL AREAS)

SECTION "C"
(ALL SHINGLE AREAS)
(APPRDX. 9,600 SQ. FT.)

ROOF PLAN

--- CENTERLINE OF 2'-0" WIDE WALKWAY PATH
APPRDX. 1,400 LINEAL FEET

General Notes



DISCLAIMER
ALL DEAD, DESIGN ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY AND ARE THE PROPERTY OF ROOFINGPROJECTS.COM AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH LOGOS, DESIGNS, ARRANGEMENTS OR PLANS SHALL BE LOANED BY OR DISCLOSED TO ANY THIRD PARTY WHATSOEVER WITHOUT THE WRITTEN PERMISSION OF ROOFINGPROJECTS.COM.
WRITTEN DIMENSIONS ON THIS DRAWING SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTOR SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS.

No.	Revision/Issue	Date

Firm Name and Address

RoofingProjects-com
17 High Street
Suite 301
Norwalk, CT
06851

Project Name and Address

2026
Jewel-Osco #3394
13200 Village Green Dr
Huntley, IL 60142

Project	Sheet
Date May 27, 2026	1
Scale 1/16" = 1'-0"	