



- EDGE CONDITIONS LEGEND:**
- E1 - REMOVE EXIST. DRIP EDGE METAL AND GUTTER. INSTALL NEW WOOD BLOCKING AND TAPERED EDGE STRIP TO MATCH HEIGHT OF NEW ROOF SYSTEM, TO PROMOTE DRAINAGE INTO GUTTER AND PREVENT PONDING ALONG ROOF EDGE. INSTALL NEW 6" X 6" BOX GUTTER W/ NEW DOWNSPOUTS TO MATCH EXISTING CONFIGURATION IN ORIGINAL LOCATIONS (SEE DET #000).
  - E2 - 2'-9" (H) TO 4'-3" (HXVARIES) X 1'-0" TO 1'-4" (WXVARIES) PARAPET WALL. REMOVE EXISTING CLAY TILE COPING AND ASSOCIATED CEMENT GROUT DOWN TO TOP OF CMU WALL. EXIST. WALL FLASHINGS TO REMAIN. REMOVE LOW METAL COUNTER FLASHING. INSTALL MECH ATTACHED 1/2" DENS DECK OVER WALL SURFACE FULL HEIGHT. INSTALL NEW P.T. WOOD BLOCKING (FULL WIDTH OF WALL) ON TOP OF CMU WALL ANCHORED IN PLACE TO MEET WIND UPLIFT RESISTANCE REQUIREMENTS. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE OF NEW BLOCKING. INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. #002).
  - E3 - 3'-0" (H) TO 3'-11" (HXVARIES) X 1'-9" (W) PARAPET WALL. REMOVE EXIST. METAL COPING AND LOW METAL COUNTER FLASHING. EXISTING WALL FLASHINGS TO REMAIN. INSTALL 1/2" MECH ATTACHED DENS DECK OVER WALL FULL HEIGHT. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE. INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. #002).
  - E4 - 5'-0" (H) WALL FLASHING. REMOVE LOW COUNTER FLASHING. EXISTING WALL FLASHING TO REMAIN. INSTALL 1/2" MECH ATTACHED DENS DECK FULL HEIGHT OF WALL. INSTALL FULLY ADHERED NEW WALL FLASHING AND INSTALL TERM BAR AND SEALANT UNDER NEW DRIP EDGE NOTED IN EDGE CONDITION E1.
  - E5 - 6" TO 5'-0" (HXVARIES) WALL FLASHING. EXISTING WALL FLASHING TO REMAIN. INSTALL 1/2" MECH ATTACHED DENS DECK FULL HEIGHT OF WALL. INSTALL FULLY ADHERED NEW WALL FLASHING FULL HEIGHT AND TIE INTO FIELD MEMBRANE ON BOTH SIDES OF VERTICAL TRANSITION.
  - E6 - LOW RISE AREA DIVIDER. EXISTING TO REMAIN. INSTALL NEW MEMBRANE OVER AND TIE INTO FIELD MEMBRANE ON BOTH SIDES.

**ROOF PLAN**

NOTE: INSTALL 1/2" MECH ATTACHED DENS DECK OVER ALL FLASHING SUBSTRATES FULL HEIGHT

- PENETRATIONS LIST:**
- CURBS**  
 A - CHILLER UNITS AND RTU'S ON 22'-50" I-BEAMS WITH (4) 6"X6" SQUARE SUPPORTS AND (2) 2'X2'6" DUCTS THRU ROOF AND (2) DUCTS THRU WALL  
 B - 4'6"X8" RTU  
 C - 5'6"X8" RTU  
 D - 4'X6'6" RTU  
 ROOF HATCH - 3'X3'6" - 2
- PIPES**  
 1" - 20  
 2" - 11  
 3" - 22  
 4" - 8  
 5" - 2
- VENT STACKS**  
 8" - 2  
 10" - 1  
 14" - 2
- RTU'S**  
 3'X3' - 3  
 19"X19" - 2
- KITCHEN EXHAUST FANS**  
 2'X2' - 5  
 2'6"X2'6" - 2
- SATELLITE DISH PADS (SET ON WALK PADS)**  
 7'X7' - 1  
 3'X3' - 1
- 8'X34' ABANDONED I-BEAMS WITH (2) 4"X4" SQUARE SUPPORTS - 1 (CUT FLUSH W/ ROOF AND REMOVE, ROOF OVER AREA)  
 CONDENSER ON (4) 2' LONG SUPPORTS - 1 (REPLACE SUPPORTS W/ NEW P.T. LUMBER TO MATCH AND SET ON WALK PADS)  
 2'X2' ABANDONED CURB - 1 (REMOVE, CLOSE OPENING IN DECK, INFILL INSULATION TO MATCH EXISTING AND ROOF OVER AREA)  
 2'X3'6" GOOSE NECK DUCT - 1  
 1'6"X3' GOOSE NECK DUCT - 1

General Notes



DISCLAIMER  
 ALL DESIGN, DESIGN ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY AND ARE THE PROPERTY OF ROOFINGPROJECTS.COM AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIC PROJECT. NONE OF SUCH DESIGN, DESIGN ARRANGEMENTS OR PLANS SHALL BE LOANED BY OR DISCLOSED TO ANY THIRD PARTY WHATSOEVER WITHOUT THE WRITTEN PERMISSION OF ROOFINGPROJECTS.COM.  
 WRITTEN DIMENSIONS ON THIS DRAWING SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS.

No.	Revision/Issue	Date

Firm Name and Address  
 RoofingProjects-com  
 17 High Street  
 Suite 301  
 Norwalk, CT  
 06851

Project Name and Address  
 2026  
 Acme #2497  
 1261 E Putnam Ave  
 Riverside, CT 06878

Project	Sheet
Date April 20, 2026	1
Scale 3/32" = 1'-0"	